



Republic of the Philippines
Department of Agriculture
AGRICULTURAL TRAINING INSTITUTE

ATI Building, Elliptical Road, Diliman, Quezon City, Metro Manila 1100
Tel. Nos. (63-2) 8929-8541 to 49 & 8928-7397 Fax No. (63-2) 8920-9792
Email: ati_director@ati.da.gov.ph & ati_director@yahoo.com
URL: http://www.ati.da.gov.ph; www.e-extension.gov.ph

PURCHASE ORDER

SUPPLIER: **DLM ENTERPRISE**
ADDRESS: 64 CORUMI ST., MASAMBONG, QUEZON CITY

P.O. No.: 2021-08-148
DATE: August 11, 2021

TIN: 269-221-154-000

MODE OF PROCUREMENT: NP-SMALL VALUE PROCUREMENT

Gentlemen:

Please furnish this Office the following article(s) subject to the terms and conditions contained herein.

Place of Delivery: ATI, Diliman, Quezon City
Delivery Terms: 120 WORKING DAY
Date of Delivery: Payment Term: LLDAP

STOCK NO.	UNIT	DESCRIPTION	QTY	UNIT COST	TOTAL COST
		FOR REPAIR WORKS AT RDEC BUILDING (PHASE-1)			
		A. REPAIR OF INFESTED ACCENT WALL WOODEN PANEL AT FUNCTION HALL & LOBBY			
	sqm	Repair of infested wall wooden panel 1. Removal of all infested wood panel & frames 2. Cleaning of area 3. Supply and installation of new ribbon grain plywood (applied with anti-termite chemical) and metal furring 4. Application of natural varnish finish	85	3,500.00	297,500.00
	lot	Application of comprehensive termit treatment	1	2,502.00	2,502.00
	lot	B. REPAIR AND REPAINTING OF CABINET DOORS AT RECEPTION Removal of blistering paint	1	1,200.00	1,200.00
	sqm	Application of enamel paint finish (interior)	10	340.00	3,400.00
	sqm	Re-application of natural varnish coating (exterior)	3	445.00	1,335.00
	pc	Soft close concealed cabinet hinges	21	261.90	5,499.90
		C. REPAIR OF WATER LEAKS AT FAÇADE			
	lot	Surface preparation for application of new waterproofing 1. Removal of steel deck strainer 2. Thoroughly clean the surface of concrete (Remove all loose materials, oil and dirt)	1	2,310.00	2,310.00
	lot	Application of sealant on pvc fitting under the concrete slab	1	1,500.00	1,500.00
	lot	Repair of cracks on concrete slab	1	2,000.00	2,000.00
	sqm	Apply 3-coats 40mil. Polymeric water proofing coating on concrete slab (Materials should be approved before application)	30	1,310.00	39,300.00
	set	Cast iron scupper drain 4"	2	304.00	608.00
		D. CLEANING OF GRANITE CLADDING & POLYCARBONATE ROOFING INCLUDING REPAINTING OF CEILING AND WOOD ACCENT AT MAIN			
	lot	Repair works for granit cladding 1. Installation of new 1pc 20x40cm & 20x60cm solid granite 2. Removal of existing epoxy on gap & application of new epoxy 3. Cleaning, application of wax & buffing of granite	1	3,500.00	3,500.00
	lot	Cleaning of polycarbonate roofing and application of sealant	1	2,102.00	2,102.00
	sqm	Supply & installation of new ribbon grain plywood and frame	2	1,500.00	3,000.00
	sqm	Application of flat latex paint of ceiling	22	309.00	6,798.00
	sqm	Application of natural varnish finish on ceiling	6	445.00	2,670.00
		E. WATERPROOFING ON CONCRETE PLANTER BOX			
	lot	Temporary remove garden soil inside concrete planter box	1	2,300.00	2,300.00
	lot	Thoroughly clean the surface of concrete (Remove all loose materials, oil and dirt)	1	2,700.00	2,700.00
	lot	Repair of cracks on concrete	1	1,500.00	1,500.00
	sqm	Apply 3-coats 40mil. Polymeric waterproofing coating on concrete slab (Materials should be approved before application)	20	1,310.00	26,200.00
	sqm	Concrete topping and plastering	20	350.00	7,000.00
		F. REPAIR AND REPAINTING OF CRACK ON CONCRETE WALL NEAR THE FIRE EXIT, AT HALLWAY, ROOM 39, ROOM 44 AND LAUNDRY AT 3RD FLOOR			
	lot	Repair and repainting of crack on concrete wall near the fire exit, at hallway, room 39, room 4 and laundry at 3rd floor 1. Chip off the cracks 2. Fill the cracks with cement mortar 3. Cement plastering of affected wall 4. repainting	1	3,505.00	3,505.00

STOCK NO.	UNIT	DESCRIPTION	QTY	UNIT COST	TOTAL COST
	lot	WATERPROOFING OF CONCRETE DECK SLAB (NEAR SERVICE STAIR) Surface preparation for application of new waterproofing 1. Removal & cleaning of steel deck strainer 2. Thoroughly clean the surface of concrete (Remove all loose materials, oil and dirt)	1	3,000.00	3,000.00
	lot	Repair of cracks on concrete slab	1	1,500.00	1,500.00
	sqm	Apply 3-coats 40mil. Polymeric waterproofing coating on concrete slab (Material should be approved before application)	70	1,310.00	91,700.00
		H. WATERPROOFING OF DECK SLAB (ABOVE MAIN STAIR) & ELEVATOR ROOF DECK SLAB			
	lot	Surface preparation for application of new waterproofing 1. Removal & cleaning of steel deck strainer 2. Thoroughly clean the surface of concrete (Remove all loose materials oil and dirt)	1	3,518.00	3,518.00
	lot	Repair of cracks on concrete slab	1	1,500.00	1,500.00
	sqm	Apply 3-coats 40mil. Polymeric waterproofing coating on concrete slab (Material should be approved before application)	65	1,310.00	85,150.00
	lot	Repair of roof gutter -Cleaning of roof gutter -Resealant of roof gutter	1	1,402.00	1,402.00
		I. OTHERS			
	lot	Temporary construction safety screen, platform, frame for perimeter fence, scaffolding and PPE's	1	5,800.00	5,800.00
	lot	Hauling of debris & Site Clearing	1	15,000.00	15,000.00
		Purpose: For repair of works at RDEC Building (Phase 1)			

TOTAL AMOUNT IN WORDS:

SIX HUNDRED TWENTY SIX THOUSAND NINE HUNDRED NINETY NINE PESOS AND 90/100 ONLY

₱ **626,999.90**

In case of failure to make the full delivery within the time specified above, a penalty of one-tenth (1/10) of one percent (1%) for everyday of delay shall be imposed.

COMFORME:

R. Silverio **SEPT. 8, 2021**
RICHARD SILVERIO
Signature Over Printed Name of Supplier

SEPTEMBER 8, 2021
Date

Very truly yours,

Alfredo S. Aton
ALFREDO S. ATON, MPS-DM
DIRECTOR IV

FUNDS AVAILABLE:

Joan E. Singson
JOAN E. SINGSON
CHIEF ACCOUNTANT

OR/BUR No.:

2021-08-76
08-20-21

Amount:

Php 626,999.90

DA-ATI
BAC-Sec.
RECEIVED

FIL 9-7-21